HASSAN DIVISION.

The 7th September 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan division, up to 27th September 1897, for constructing Dispensary at Konanur, Arkalgud taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of October 1898.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Hassan between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and be accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Dispensary at Konanur, Arkalgud taluk"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items.	*Per.*	*Quantity.*
Excavation	C. yds.	122
Burnt stone in chunam	C. ft.	4,351
Burnt brick do	,,	1,293
Do in clay	,,	4,304
Archwork	,,	79
Burnt stone slabs	S. ft.	412
Plastering in chunam	Sqr.	87·03
Pointing do	,,	4.79
Whitewashing 2 coats	,,	58·62
Color do	,,	0·90
Flooring with concrete and plastered over	,,	0·64
Teak wood work wrought and put up	C. ft.	167·72
Honne wood work do	,,	35·96
Roofing with Mangalore flat tiles and teak reepers, &c.	Sqr.	34·32
Ridging with Mangalore ridge tiles	R. ft.	103⅞
Ventilating tiles	Each.	16
Coping with burnt brick in chunam and plastered over	R. ft.	39½
Teak wood doors and windows with pannelled shutters	..	..
Do windows with frames secured with iron bars (¾″)	..	..
Junglewood doors 2½ × 5½	Each.	1
Do do	,,	1
Do windows 1½ × 1¾	,,	1
Do do	,,	4
Platform slabs	C. ft.	11
Honeycomb work	Sqr.	2·46
Stone pillars	Each.	10
Teak eave boards	R. ft.	302
Red painting	Sqr.	7·00
Wood oiling	,,	13·00
Tarring	Lump Sum.	
Date stone	..	
Clearing site	..	
Compensation for land	..	
Flooring with Mangalore flooring tiles	Sqr.	13·37